

6/23/2022

**Request for Quote for
Port Allegany School District
20 OAK ST
Port Allegany, PA 16743**

Project Intent and Scope

The Port Allegany School District is looking to expand its current camera system. This request is for both hardware and installation of systems. To maintain system continuity, it is requested that any respondent use the manufacturers, and relative part numbers below. Descriptions of each are detailed below:

Camera System Hardware/Software: Current system uses Vivotek Milestone systems and request same or compatible technologies. The provider/bidder would need to provide a quote for all hardware/software listed in the table below.

Item	Part#	Quantity
43In Bet Series Commercial Tv Crystal Uhd	Samsung - Part#: BE43T-H	2
StarTech.com TV Wall Mount	StarTech.com - Part#: FPWARTS1	2
Hanwha Techwin WiseNet SPD-150 - Video decoder	Hanwha Techwin - Part#: SPD-150	2
3 ft Slim High Speed HDMI Cable with Ethernet	StarTech.com - Part#: HDMIMM3HSS	2
Vivotek Indoor Dome 2MP Camera	Vivotek - Part#: FD9167-HT-V2	9
Vivotek C Series FD9369 - Network surveillance camera - Outdoor	Vivotek - Part#: FD9369	12
Milestone Care Plus - Technical support - for XProtect Professional+	Milestone Systems - Part#: Y2XPPPLUSDL-35	68
XProtect Professional+ - Device License	Milestone Systems - Part#: XPPPLUSBL-35	21
AAC license for 1 XP Smart	Milestone Systems - Part#: XPAACL	21
XProtect Professional+ - Base License - 35 licenses - Win	Milestone Systems - Part#: XPPPLUSBL-35	1
CONDUIT BOX FOR IB9360-H	Part#: AM-71E-V02	12
Tripp Lite 24-Port 1U Rack-Mount Shielded Blank Keystone/Multimedia Patch Panel	Tripp Lite - Part#: N062-024-KJ-SH	7
C2G 3ft Cat6 Ethernt Cable - Snagless Unshielded	C2G - Part#: 27181	21
C2G 1ft Cat6 Snagless Unshielded	C2G - Part#: 27180	21
Cat6 Cable 1000ft	Plenum rated CAT6	4

Installation of Security Cameras: The provider/installer would be responsible for ALL activities listed in the "Provider Responsibilities" section.

Provider Responsibilities:

Provider will be responsible for the following tasks

- Physical installation of Cameras in every targeted location:
 - Capture S/N, MAC Address, with corresponding room numbers/area description
 - Label devices
 - Mounted to ceiling or wall, unless otherwise specified
 - Cable enclosed in indoor/outdoor raceway/conduit (if required). Provider to supply raceway/conduit
- Installation of network drops required for the cameras, including:
 - Pulling of ALL CAT6 cable to ALL camera locations
 - Terminating cable ends (patch panel, male, or female)
- Work with client IT department to validate camera connectivity and imaging in all targeted areas, including:
 - Proper IP address
 - Connectivity and management capability via management software
 - Focus
 - Angle/coverage accuracy
- All work list above, with specific quantities to be delivered at the following:
 - High School
 - **7 Indoor cameras**
 - **7 Outdoor cameras**
 - Elementary School
 - **2 Indoor camera**
 - **5 outdoor cameras**
- Breakdown and remove all garbage from installation
 - Place recyclable material in designated bins

Client Responsibilities:

With respect to project completion, the client will be responsible for the following:

- Procurement of all hardware
- Providing access to all buildings during agreed to working hours
- Scheduling of services
- Provide knowledgeable key personnel who will be responsible for questions, sign off, entry, timely decisions necessary to move performance of services forward during times of install
- Inform Provider of any hazardous conditions on premises. In particular Provider needs to be aware of any asbestos in the vicinity of the proposed implementation. Confirmation of the presence or absence of asbestos must be received before any work can be undertaken.

Quotes will be accepted through 3:00PM Thursday, July 28, 2022. The Port Allegany Board of Directors is expected to take action on this camera project on Monday, August 1, 2022 at the scheduled meeting.

Please feel free to contact PASD at (814) 642-2596 and reference camera quote with any questions.